



GENERAL NOTES

- 1. THIS ROLL-UP DOOR SYSTEM IS DESIGNED IN ACCORDANCE WITH THE FLORIDA
- 2. THIS ROLL-UP DOOR HAS BEEN TESTED IN ACCORDANCE WITH ASTM E-330 AND COMPLIES WITH ANSI/DASMA 108.

DESIGN LOAD =
$$^{+19.4}_{-22.7}$$
 PSF

- 3. WIND LOADS FOR BUILDING OPENINGS SHALL BE DETERMINED BY A PROFESSIONAL ENGINEER USING APPROPRIATE WIND SPEED AND DESIGN CRITERIA. THIS DOOR MAY BE USED WHERE THE DESIGN LOAD MEETS OR EXCEEDS THE DESIGN LOAD FOR THE
- 4. SUPERIMPOSED LOADS ON THE JAMBS FROM THIS DOOR ARE DESIGNED AS Vx AND Vy HEREIN. CONTRACTORS SHALL HAVE BUILDING ENGINEER VERIFY ADEQUACY OF BUILDING STRUCTURE TO RESIST SUPERIMPOSED LOADS $\forall x, \forall y, \text{ AND BRACKET LOADS}$
- 5. ALL WELDING SHALL BE PERFORMED BY QUALIFIED WELDERS IN ACCORDANCE WITH A.W.S. SPECIFICATIONS, LATEST EDITION. ALL WELDING ELECTRODES SHALL CONFORM TO A.W.S. A5.1 GRADE E-70.
- 6. DOORS SHALL BE PROVIDED WITH LOCK MECHANISMS AT THE OPTION OF THE OWNER.
- 7. ALL BOLTS AND WASHERS SHALL BE GALVANIZED OR STAINLESS STEEL WITH A MINIMUM TENSILE STRENGTH OF 60 KSI.
- 8. DESIGN BASED ON UNDERWRITERS LABORITORIES TEST REPORT NO. SV30743-20161010-REPORT4

- 9 ANCHOR NOTES:
- EMBEDMENT LENGTH DOES NOT INCLUDE STUCCO FINISH.
- FOR HOLLOW MASONRY, FILL ALL CELLS @ ANCHOR WITH 2500 PSI GROUT. ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S **SPECIFICATIONS**
- 10. DOOR OPERATION TYPED TO BE PUSH-UP.
- 11. GUIDE TO JAMB ATTACHMENT FASTENERS BEGIN 4" FROM FLOOR AND END 3-1/2" BELOW TOP OF WALL OPENING.
- 12. TEST DOOR WALL OPENING SIZE: 10'-0" X 8'-0"

John E. Scates, P.E. 3121 Fairgate Dr. Carrollton, TX 75007 FL PE 51737

Professional Engineer's seal provided only for verification of windload construction details

			instruction details.					
THESE CONFIDENTIAL DOCUMENTS SUBMITTED BY JANUS CONTAIN INFORMATION OF A PROPRIETARY NATURE AND MAY NOT BE REPRODUCED OR USED TO MANUFACTURE ANYTHING IN PART OR IN WHOLE FOR ANY PURPOSE OTHER THAN THAT WHICH IS NECESSARY FOR PREPARATION OF BIDS OF ENGINEERING WITHOUT THE EXPRESS PERMISSION OF JANUS WHICH MAY RECALL DOCUMENTS AT ANY TIME. UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES AND TOLERANCES ARE:						JANUS INTERNATIONAL CORPORATION		
						135 JANUS INTERNATIONAL BLVD. TEMPLE, GA 30179-4435		
				UNIT OF MEASURE:		CERTIFIED WIND LOAD BATED		
DECIMAL	FRACTIONS	ANGLES	HOLE DIAMETERS	APPROVALS	DATE	CERTIFIED WIND LOAD RATED 26 GA SERIES 750 DOOR ASSEMBLY		
.XX ±.03 .XXX ±.005	<u>+</u> 1/16	± 0° 30'	UNDER 0.251 + .004	BECKY NELSON	11-14-02	MAY SIZE: 10'-0" X 12'-0"		
			0.251 to 0.500 ^{+.006} ₀₀₃	CHECKED: DON MILLS	11-14-02	T4000	D REV:	
			OVER 0.500 ^{+.008} ₀₀₃	APPROVED: DON MILLS	11-14-02	SCALE: NONE SHEET: OF: 2 2		